

**CONTRACTOR'S SUBMITTAL TRANSMITTAL**  
5ND LANTDIV 4-4355/3 (Rev. 6/76)

*Falt*

FROM CONTRACTOR <b>Trader Construction Company</b>	CONTRACT NO. <b>81-C-1766</b>	TRANSMITTAL NO. <b>49A</b>	DATE <b>28 NOV 83</b>
TO <b>Lockwood Greene/Six Associates</b>	PROJECT TITLE AND LOCATION <b>Public Works &amp; Helipad MCB Camp Lejeune, NC</b>		

**CONTRACTOR USE ONLY**

*List only one specification division per form.*

*List only one of the following categories on each transmittal form, and indicate which is being submitted*

- Contractor Approved
- OICC Approval
- Deviation/Substitution For OICC Approval

**REVIEWER USE ONLY**

**\*\*ACTION CODES**  
A-Approved  
D-Disapproved  
AN-Approved as noted  
RA-Receipt acknowledged.  
C-Comments  
R-Resubmit

ITEM NO.	PROJ. SPEC. SECT. & PARA. and/or PROJ. DWG. NO.	ITEM IDENTIFICATION (Type, size, model no., Mfg. name, dwg. or brochure number)	NO. OF COPIES	ACTION CODES	REVIEWER'S INITIALS CODE AND DATE
127	07160 3.2	Bit. Dampproofing			
	2.1	Karnak, Asphalt Primer#108, Catalog Data	7	A	A.B. 2 Dec 83
		" " " Certification	7	A	" "

CONTRACTOR'S COMMENTS

*Copy - Filed 12-14-83*

RECEIVED  
ROICC JAXNCAI  
DEC 12 1 13 PM '83

COPY OF TRANSMITTAL AND SUBMITTALS TO ROICC  
**ROICC, Camp Lejeune, NC**

CONTRACTOR REPRESENTATIVE (Signature)  
*John M...*

DATE RECEIVED BY REVIEWER  
**12/1/83**

FROM (Reviewer)  
**Six Associates, Inc.**

TO  
**Trader Construction Co.**

- Submittals are returned with action indicated. Approval of an item does not include approval of any deviation from the contract requirements unless the contractor calls attention to and supports the deviation.
- Submittals are forwarded to LANTDIV with A-E recommendations indicated in REVIEWER USE ONLY Section and in comments below on ONE COPY of the transmittal form.

REVIEWER'S COMMENTS


NAVFAC letter dated 19 May 83 requires five transmittal forms.

1		
2	YO	L
3		
4		
5		
6		
7		
8		

COPIES TO:  
ROICC (2) ✓  
LANTDIV (1)  
A-E (1)

DATE  
**12/8/83**

SIGNATURE  
*A.B. Joh*





# KARNAK CHEMICAL CORPORATION

(LEWIS ASPHALT ENGINEERING CORPORATION)

330 Central Avenue • Clark, N. J. • Telephone 201 - 388-0300

Date: Nov. 18, 1983

## CERTIFICATE OF COMPLIANCE

**For:** Trader Construction Co.  
P.O. Drawer 1578  
New Bern, N.C. 28560

**Project:** Public Works Building  
MCB Camp Lejune  
# N62470-81-C-1766

Attn: Jack Leavel

**Materials:**

This is to certify that Karnak #108 Asphalt Primer complies with ASTM D-4173

"It is hereby certified that the (equipment) (material) shown and marked in this submittal is that proposed to be incorporated into Contract Number N62470-81-C-1766, is in compliance with the Contract drawings and specifications, can be installed in the allocated spaces, and is submitted Government approval.

Certified by \_\_\_\_\_ *[Signature]*

Date 29 Nov 83 "

JM:sm  
cc: Dixie Forming

ATLANTIC DIVISION  
NAVAL FACILITIES ENGINEERING COMMAND  
NORFOLK, VIRGINIA 23511

APPROVED \_\_\_\_\_  
APPROVED AS NOTED \_\_\_\_\_  
DISAPPROVED \_\_\_\_\_

SUBJECT TO THE REQUIREMENTS OF  
CONTRACT NO. N62470-81-C-1766

APPROVAL OF A SUBMITTAL DOES NOT INCLUDE APPROVAL OF ANY DEVIATION FROM THE CONTRACT REQUIREMENTS UNLESS THE CONTRACTOR CALLS ATTENTION TO AND SUPPORTS THE DEVIATION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING PROPER PHYSICAL DIMENSIONS & WEIGHTS, COORDINATION OF TRADES, ETC., AS REQUIRED.

REVIEWER *[Signature]* DATE 2 Dec 83


FOR OFFICER IN CHARGE OF CONSTRUCTION

*[Signature]*  
NOTARY PUBLIC  
NEW JERSEY  
My Commission Expires Sept. 28, 1988



I hereby certify this to be a true and accurate statement.

*[Signature]*  
Jerry Mills - Asst. Sales Mgr.





It is hereby certified that the (equipment) (material) shown and marked in this submittal is that proposed to be incorporated into Contract Number N62470-81-C-1766 is in compliance with the Contract drawings and specifications, as they are called in the allocated spaces, and is submitted Government approval.

Certified by \_\_\_\_\_ *Jm*

Date \_\_\_\_\_ *29 Nov 83* "

**product data** DISTRIBUTED BY

**DIXIE FORMING & BUILDING SPECIALTIES, INC.**

P. O. BOX 27046

RALEIGH, N. C. 27611

PHONE: 919-832-0592

800-662-7147 N. C. WATS

800-334-7710 VA. & S. C. WATS

## No. 108 ASPHALT PRIMER

GENERAL PURPOSE, PENETRATION ASPHALT PRIMER USED FOR THE PREPARATION OF ALL TYPES OF SURFACES PREVIOUS TO THE APPLICATION OF HOT OR COLD ASPHALT COATINGS — BRUSH OR SPRAY APPLICATION

Complies with: Federal Specification SS-A-701 and A.S.T.M. Specification 41-73.

### DESCRIPTION:

#108 Asphalt Primer is a thin preparation of a highly ductile, soft asphalt in a selected hydrocarbon solvent. It is especially designed for use as a general utility prime coat for concrete, gypsum, masonry, brick and metal surfaces, over which waterproofing, damproofing, roof coatings and other asphalt products are to be applied. This thin solution readily penetrates the pores and seals dusty masonry surfaces to provide a firm base for such coatings. It is specified as a primer coat previous to the application of the membrane system of waterproofing on all concrete structures. It is also very efficiently used as a felt saturant on old dried out built-up roofs where extreme penetration is required to re-vitalize the base surfaces before the application of roof coatings.

### APPLICATION:

All surfaces to be primed with Karnak #108 Asphalt Primer must be dry and free from oil, grease, dust, dirt and any other foreign matter.

### COVERAGE:

Karnak #108 Asphalt Primer is easily applied by brush or spray equipment at the rate of 1 to 1½ gallons per 100 sq. ft. depending entirely upon the porosity and type of surface being primed. Masonry and dried out built-up roof structures should be liberally applied to obtain the most penetration so than effective bond can be made for the covering material.

### CAUTION:

Karnak Asphalt Primer is inflammable. Do not use near open flame and provide adequate ventilation for the protection of the applicators from solvent fumes. The steel containers should be covered when not in use. Spray equipment, brushes and other tools may be cleaned and the dried asphaltic primer removed by the use of mineral spirits.

### PACKAGING:

Available in 55-gallon drums and 5-gallon pails.

**Karnak Chemical Corp.**

**Karnak Chemical Corp. of Illinois**

212—267-6226 201—388-0300  
330 CENTRAL AVENUE, CLARK, N.J. 07066

312—755-7778  
250 E. 17th ST., CHICAGO HEIGHTS, ILL. 60411

Outside of N.Y./N.J./Chicago Call Toll Free: 800—526-4236

*The above suggested recommendations for use of Karnak products are predicated on tests believed to be reliable. However, since such application and use is beyond our control, we do not guarantee the results to be obtained.*

