

## FILE FOLDER

### DESCRIPTION ON TAB:

Adkins's Copy AS-110

---

---

**Outside/inside of actual folder did not contain hand written information**

**Outside/inside of actual folder did contain hand written information**

**\*Scanned as next image**

ADKINS  
AS-110

0


ADKINS

Water Treatment Branch at Camp Lejeune, North Carolina consists of 3 lime softening plants, and 3 ion exchange plants, all supplied by 92 deep wells. These plants have a combined capacity of 15,150,000 gallons per day. We also check and operate 7 swimming pools.

INDIVIDUAL PLANT CAPACITIES

Hadnot Point	5.0 M.G.D.	"A" Well	Serial # 04-67-041
Holcomb Blvd.	5.0 M.G.D.	" " Well	Serial # 04-67-043
MCAS	3.5 M.G.D.	"B" Well	Serial # 04-67-042
<del>Rifle Range</del>	<del>.600 M.G.D.</del>	<del>"B" Well</del>	<del>Serial # 04-67-046</del>
Courthouse Bay	.800 M.G.D.	"B" Well	Serial # 04-67-047
Onslow Beach	.250 M.G.D.	"B" Well	Serial # 04-67-048

There are 42 personnel, consisting of operators, mechanics, swimming pool operators and helpers maintaining these facilities which are regulated by the State of North Carolina.



WATER TREATMENT

1,762 MILES OF DISTRIBUTION LINES  
1,000 MILES OF RAW WATER LINES  
1,142 FIRE HYDRANTS  
10,000 UNDERGROUND VALVES  
7 SWIMMING POOLS  
83 WELLS IN SERVICE  
6 WATER PLANTS

PLANT CAPACITIES


Holcolm Blvd.	5,000,000
Hadnot Point	5,000,000
Courthouse Bay	800,000
<del>Rifle Range</del>	<del>600,000</del>
Onslow Beach	250,000
Air Station	<del>3,500,000</del>
TOTAL	15,150,000 PER DAY

TOTAL DELIVERED WATER FLOW FOR F/Y 1987 WAS 2,236,308,000 GALLONS.

42 PEOPLE

OPERATION IS 24 HOURS A DAY 365 DAYS A YEAR.

TOTAL STORAGE CAPACITY - 15,400,000



WASTEWATER TREATMENT

1,500 MILES OF SEWAGE LINES

69 LIFT STATIONS

15 OIL AND WATER SEPARATORS WITH MOTORS


PLANT CAPACITIES

Hadnot Point	8,000,000
<del>Camp Geiger</del>	<del>1,600,000</del>
<del>Tarawa Terrace</del>	<del>1,250,000</del>
Camp Johnson	1,000,000
Courthouse Bay	8,600,000
<del>Rifle Range</del>	<del>525,000</del>
<del>Onslow Beach</del>	<del>195,000</del>
TOTAL	<sup>13</sup> 18,560,000

TOTAL FLOW FOR F/Y 1987 WAS 3,016,337,732 GALLONS.

44 PEOPLE

OPERATION IS 24 HOURS A DAY 365 DAYS A YEAR.



STORAGE TANKS - GROUND & ELEVATED

A. HADNOT POINT AREA

S-735 ----- 500,000 Capacity (Ground) (Treated) ✓  
S-763 ----- 2,000,000 " " (Treated) ✓  
B-20 ----- 800,000 " " (Raw)

ELEVATED TANKS

S-5 ----- 300,000 Capacity, Area #2 ✓  
S-29 ----- 300,000 " , Area #5 ✓  
S-1000 ----- 300,000 " , Industrial ✓  
FC-314 ----- 300,000 " , Force Troops ✓

B. HOLCOMB BLVD. AREA

S-671 ----- 1,000,000 Capacity (Ground) (Treated) ✓  
<sup>2,000,000</sup> " " " " " " ✓  
<sup>1,000,000</sup> " " " " " " ✓

ELEVATED TANKS

S-830 ----- 300,000 Capacity, Berkley Manor ✓  
S-2323 ----- 200,000 Capacity, Paradise Point ✓  
S-4004 ----- 200,000 " , Midway Park ✓

C. TARAWA TERRACE AREA

STT-39 ----- 750,000 Capacity (Ground) Treated ✓  
STT-40 ----- 250,000 Capacity (Elevated) ✓

D. MONTFORD POINT AREA


SM-179 ----- 400,000 Capacity (Ground) Treated ✓  
SM-624 ----- 150,000 Capacity (Elevated) Treated ✓

E. MCAS AREA

~~MCAS-108 -- 200,000 Capacity (Ground) Treated ✓~~  
~~MCAS-107 -- 225,000 " " " " ✓~~  
<sup>AS 2010 300</sup> //  
MCAS-310 -- 300,000 Capacity (Elevated) ✓  
MCAS-4130 - 350,000 Capacity (Elevated) ✓ - white  
~~MOQ-2002 -- 300,000 Capacity (Ground) Emergency Station ✓~~

CAMP GEIGER

~~STC-500 --- 272,000 Capacity (Ground) Treated from MCAS ✓~~  
~~STC-509 --- 600,000 Capacity (Ground) " " " " ✓~~



CAMP GEIGER (Con'T)

~~STC-606~~ ---- 100,000 Capacity (Elevated) ✓  
~~STC-1070~~ ---- 100,000 Capacity (Elevated) ✓

TC 510, 500,000 BL

F. RIFLE RANGE AREA

~~SRR-86~~ ----- 360,000 Capacity (Ground) ✓

~~SRR-44~~ ----- 100,000 Capacity (Elevated) ✓

G. COURTHOUSE BAY AREA

~~SBB-191~~ ----- 350,000 Capacity (Ground) ✓


~~SBB-25~~ ----- 100,000 Capacity (Elevated) ✓  
325,000 " " "

ON SLOW BEACH AREA

~~SBA-139~~ ---- 250,000 Capacity (Ground) ✓

~~SBA-108~~ ---- 100,000 Capacity (Elevated) ✓


I. ~~Amphibian Base~~ -- 6,000 Capacity Pressure Tank (Emergency)





MAY 25 1989


PROCEDURE FOR BACKWASHING FILTERS - BLDG 20


- Step 1. Close influent valve. Turn rate-of-flow on other filters in use up to maintain proper water level in re-carb. Do not exceed maximum filter capacity. (It may require another filter to be placed in service.)
- Step 2. Allow filter to operate until water level reaches 6 inches from filter bed. Close rate-of-flow valve and filter effluent valve.
- Step 3. Open waste valve when water reaches top of trough.
- Step 4. Open surface wash valve and hose down filter walls and troughs.
- Step 5. (Start backwash pump first) Then open wash valve slowly, wash for 6 minutes or until filter is clear. Close surface wash valve 2 minutes prior to ending backwash cycle. Close wash valve slowly - when almost closed, stop backwash pump.
- Step 6. Close waste valve.
- Step 7. Open influent valve.
- Step 8. Return all filters in service to their normal setting.
- Step 9. Open rewash valve and rinse for 3 minutes (this not only rinses filter, it also settles filter bed).
- Step 10. Open effluent valve. Return rate-of-valve to proper setting.











TO CUT ON 24" MAIN  
FROM 670 TO 20

OPEN VALVES

MAIN VALVE 4" VALVE

GUARD RAILS

TO 8-20

WALLACE CREEK

24" DANGER WATER MAIN


12" BLOW OFF


GUARD RAILS


MAIN VALVE 4" VALVE


THIS VALVE OPEN


TO 670














INDIVIDUAL PLANT DATA

PIANT NO. & LOCATION Marine Corp Air Station MCAS 110

The Air Station Plant is a lime softening plant with a capacity of 3.5 M.G.D., and is supplied water from 23 deep wells. The plant consists of the following equipment:


1. 2 Spiractors at 1200 G.P.M. *EA*
2. 3 Filters at 800 G.P.M. gradual delivery rate *EA*
3. ~~2 Raw water booster pumps, 1200 G.P.M. each~~
4. ~~3 Treated water clearwell booster pumps, 1 at 350 G.P.M., 1 at 600 G.P.M., and 1 at 900 G.P.M.~~
5. ~~3 High service pumps, 2 at 1000 G.P.M., and 1 at 500 G.P.M.~~
6. 1 Lime silo-40 tons
7. ~~1 day bin-17 ton~~
8. 2 Lime pumps at 245 G.P.H.
9. 2 Wallace & Tiernan chlorinators
10. 2 Backwash pumps at 6000 G.P.M.
11. 2 Surface wash pumps at 350 G.P.M.
12. ~~1 Recarbonation unit-Ozark Mahoning, 750 psi of CO<sub>2</sub>/24 hrs.~~
13. 1 Generator Detroit 375 kva
14. ~~2 Treated water reservoirs, 1 at 200,000 gallons AS-107, and 1 at 225,000 gallons, AS-108.~~
15. 2 Elevated tanks, 1 at 300,000 gallons AS-310, and 1 at 350,000 gallons AS-4130.

MOQ 2002 PUMPING STATION

1. ~~1 Reservoir at 300,000 gallons~~
2. ~~4 High service pumps, 2 at 125 G.P.M., and 2 at 750 G.P.M.~~

CAMP GEIGER PUMPING STATION TC-501

1. 3 High service pumps at 700 G.P.M. each
2. 2 Treated water reservoirs, 1 at 272,000 gallons STC500, and 1 at 600,000 gallons STC509.
3. ~~2 Elevated tanks at 100,000 gallons each, STC1070 & STC606.~~
4. ~~1 International gasoline auxiliary engine~~




WATER TREATMENT PLANT


INDIVIDUAL PLANT DATA


PLANT NO. & LOCATION Marine Corps Air Station WELLS

Raw water wells included in the treatment system:


<u>A.S.WELLS</u> <u>BLDG. NO.</u>	<u>G.P.M.</u>	<u>AUXILIARY</u> <u>ENGINE</u>	<u>MANUFACTURE</u>
106	226 H/C cont.		
131	285 H/C cont.		
190	250	Diesel	Ford
191	250 H/C		
203	207 H/C		
4140	100 H/C		
4150	128 cont.		
5001	137		
5009	115		
<u>C.G.WELLS</u>			
325	100	Diesel	Murphy
502	400 H/C	Gasoline	Ford
504	250	Diesel	Ford
600	167 H/C		
604	151		
700	100		
901	100		
1000	200		
1001	170	Gasoline	Wisconsin
1251	190	Gasoline	Ford
1252 (booster pump)	2-1400		
1253	185		
1254	152		
1255	100	Gasoline	Ford
1256	104		













CAMP COOLER TUMPLING STILL  
FC - 501







MARINE CORPS AIR  
CAPACITY 3.5 M.  
LIME SOFT.

PRE-CHLORINATION


VARIABLE  
DECLINING  
RATE FILTERS






ATION - BLDG. MCAS-110

26 DEEP WELLS  
125 FT.










Table III C 3  
WELL SURVEY SHEET

Sheet No. 7

DATE: 20 June 1984

WELL NO.	WELL TYPE	DRILLED DEPTH ft.	STATIC LEVEL (ft)	CASING SIZE (in.)	STAGES	DRAWDOWN AT RATED CAPACITY (feet)	RATED CAPACITY (gpm)	PRESENT CAPACITY (gpm)
TC-100	DRILLED	66'	19'	8"	6	10'	75	75
TC-201	DRILLED	67'	15'	8"	3	44'	150	100
TC-502	DRILLED	184'	27'	8"	4	9"	300	250
TC-504	DRILLED	100'	22'	8"	3	38'	250	150
TC-600	DRILLED	70'	8'	8"	3	28'	130	75
-604	DRILLED	138'	17'	8"	4	35'	150	100
TC-700	DRILLED	76'	23'	8"	4	21'	125	75
-1000	DRILLED	170'	10'	8"	4	37'	200	150
TC-1001	DRILLED	100'	25'	8"	5	20'	220	150
STC-190	DRILLED	200'	23.11'	8"	4		250	
STC-191	DRILLED	200'	23.4'	8"	4		250	
STC-325	DRILLED	180'	40'	8"		12'	150	
STC-1251	DRILLED	180'	14.9	8"	8	25'	150	
STC-1253	DRILLED	180'	18.6	8"	7	29.1'	150	

WELL NO.	SPECIFIC CAPACITY (gpm/ft of drawdown)	PUMP HEAD (ft)	MOTOR H. P.	CHLORINATION (AMOUNT)	RESIDUAL CHLORINE (TYPE)	AUXILIARY POWER (TYPE)	DD FORM	
							710	636
TC-100	7.5	80'	3.0					
TC-201	3.4	57'	5.0					
TC-502	33.3	112'	10.0			GASOLINE		
TC-504	6.6	66'	7.5			GASOLINE		
TC-600	4.6	58'	3.0					
TC-604	4.3	65'	5.0					
TC-700	5.9	70'	3.0					
TC-1000	5.4	65'	5.0					
TC-1001	11.0	61'	5.0			GASOLINE		
STC-190		91'	10.0			DIESEL		
STC-191		81'	10.0					
STC-325	12.5	60'	5.0					
STC-1251	6	110'	7.5			GASOLINE		
STC-1253	5.15	90'	5.0					





Table III C 3  
WELL SURVEY SHEET

Sheet No. 7 cont'd

DATE: 20 June 1984

WELL NO.	WELL TYPE	DRILLED DEPTH ft.	STATIC LEVEL (ft)	CASING SIZE (in.)	STAGES	DRAWDOWN AT RATED CAPACITY (feet)	RATED CAPACITY (gpm)	PRESENT CAPACITY (gpm)
STC-1254	DRILLED	195'	24'	8"	7	4'	150	
STC-1255	DRILLED	200'	23.11	8"		25.1'	150	
STC-1256	DRILLED	200'	25'	8"		38'	150	

WELL NO.	SPECIFIC CAPACITY (gpm/ft of drawdown)	PUMP HEAD (ft)	MOTOR H. P.	CHLORINATION (AMOUNT)	RESIDUAL CHLORINE (TYPE)	AUXILIARY POWER ((TYPE)	DD FORM	
							710	636
STC-1254	37.5	90'	5.0			GASOLINE		
STC-1255	5.9	90'	5.0					
STC-1256	3.9	90'	5.0					



## WATER TREATMENT PLANT

### INDIVIDUAL PLANT DATA


PLANT NO. & LOCATION Holcomb Blvd. Bldg. 670

The Holcomb Blvd. Plant is a lime softening plant with a capacity of 5.0 M.G.D., and is supplied water from 18 deep wells. The plant consists of the following equipment:


1. 5 Spiractors at 700 G.P.M. each
2. 5 Rapid sand filters at 700 G.P.M. each
3. 4 Raw water pumps, 2 at 1400 G.P.M., 2 at 2100 G.P.M.
4. 5 Holcomb High service pumps, 2 at 700 G.P.M., 2 at 1500 G.P.M., and 1 at 3500 G.P.M.
5. 3 Transmission Main High Service Pumps, 2 at 1400 G.P.M., and 1 at 2800 G.P.M.
6. 1 - 2 million gallon raw water reservoir
7. 2 Treated water reservoirs, 1 at 1 million gallons & 1 at 2 million gallons.
8. 2 Lime storage silo's 40 tons each
9. 2 - 500 pounds per day Lime feeders
10. 6 - 245 G.P.H. Lime pumps
11. 1 Wallace & Tiernan volumetric Fluoride feeder
12. 3 Wallace & Tiernan Chlorinators, 2 at 100 lbs/day, and 1 at 200 lbs/day
13. 2 Backwash pumps at 7500 G.P.M. each
14. 2 Generators, 1 Waukesha 6 cylinder, gas, 85 kw, & 1 Cummins diesel, 6 cyl. 400 kw.
15. 1 Ford 8 cyl., gas, and 1 Ford 6 cyl, gas auxiliary engines
16. 3 Elevated tanks, 2 at 200,000 gallons and 1 at 300,000 gallons

#### TARAWA TERRACE PUMPING STATION

1. 1 Treated water reservoir, STT-39, at 750,000 gallons
2. 4 High service pumps, 1 at 750 G.P.M., 1 at 850 G.P.M., 1 at 1200 G.P.M., 1 at 2000 G.P.M.
3. 2 Elevated tanks, 1 at 250,000 gallon, STT-40, 1 at 150,000 gallon, SM-624.
4. 1 Generator, Catapillar Diesel, 255 kw.







WELL SURVEY SHEET\*

Sheet No. 4


DATE: 3-3-77

WELL NO.	WELL TYPE	DRILLED DEPTH (ft.)	STATIC LEVEL (ft)	CASING SIZE (in.)	STAGES	DRAWDOWN AT RATED CAPACITY (feet)	RATED CAPACITY (gpm)	PRESERV CAPACI (GPM)
HB-643	DRILLED	245'	24'	10"	4	36'	260	250
HB-644	DRILLED	255'	22'	10"	5	44'	260	280
HB-645	DRILLED	270'	18'	10"	4	34'	260	200
HB-646	DRILLED	270'	17'	10"	3	28'	260	150
B-647	DRILLED	200'	24"	10"	3	25'	260	200
HB-648	DRILLED	265'	22'	10"	4	77'	230	200
HB-649	DRILLED	284'	24'	10"	5	65'	400	300
HB-650	DRILLED	179'	15'	10"	5	74'	260	225

1  
2  
3  
4  
5  
6  
7  
8  
9  
10

WELL NO.	SPECIFIC CAPACITY (gpm/ft of drawdown)	PUMP HEAD (ft)	MOTOR H. P.	CHLORINATION (AMOUNT)	RESIDUAL CHLORINE (ppm)	AUXILIARY POWER (type)	DD FORM	
							710	686
HB-643	7.2	124'	15.0			GASOLINE		
HB-644	5.9	133'	15.0					
HB-645	7.6	103'	10.0			GASOLINE		
HB-646	9.3	75'	10.0			GASOLINE		
HB-647	10.4	91'	10.0			GASOLINE		
HB-648	2.9	184'	20.0					
HB-649	6.2	199'	20.0					
HB-650	3.5	210'	40.0					

1  
2  
3  
4  
5  
6  
7  
8  
9  
10



WATER TREATMENT PLANT

INDIVIDUAL PLANT DATA

PLANT NO. & LOCATION Holcomb Blvd. Swimming Pools

The Holcomb Blvd. Plant personnel is responsible for checking and maintaining the following swimming pools:


1. Area #2 pool, bldg. 236, 440,000 gallon capacity
2. 1 filter pump at 1200 G.P.M.
3. 3 filters at 400 G.P.M. each
4. 1 Wallace & Tiernan chlorinator
5. 1 Strantrol
6. 1 Backwash holding tank S-256

1. Area #5 pool, bldg. 540, 440,000 gallon capacity
2. 1 filter pump at 1200 G.P.M.
3. 3 filters at 400 G.P.M. each
4. 1 Wallace & Tiernan chlorinator
5. 1 Strantrol
6. 1 backwash holding tank S-563

1. Paradise Point pool, bldg. 2632, bldg. 2631 (baby pool), 188,000 gallon capacity
2. 1 Filter pump at 600 G.P.M.
3. 3 Filters at 200 G.P.M. each
4. 1 Wallace & Tiernan chlorinator
5. 1 Strantrol

1. Tarawa Terrace pool, TT-20, 298,000 gallon capacity
2. 1 filter, 3 cells, 50 sq. ft./cell, flow rate 5.59 gal/sq.ft./min.
3. 1 filter pump at 830 G.P.M.
4. 1 Stantrol
5. 1 Wallace & Tiernan chlorinator

1. Camp Johnson pool, M-178, 440,000 gallon capacity
2. 3 filters at 400 G.P.M. each
3. 1 Filter pump at 1200 G.P.M.
4. 1 Wallace & Tiernan chlorinator
5. 1 Strantrol
6. 1 Backwash holding tank



WATER TREATMENT PLANT


INDIVIDUAL PLANT DATA

PIANT NO. & LOCATION Marine Corps Air Station Swimming Pools


The Air Station plant personnel is responsible for checking and maintaining the following pools:


1. Enlisted Pool, AS-204, 288,000 gallon capacity
2. 6 Pressure sand filters at 140 G.P.M. each
3. 2 Filter pumps at 600 G.P.M. each
4. 1 Chlorinator, Advance
5. 1 Strantrol

1. Officer's pool, AS-709, 110,000 gallon capacity
2. 2 Filters at 140 G.P.M. each
3. 1 Filter pump at 238 G.P.M.
4. 1 Chlorinator, Advance
5. 1 Strantrol



PARADISE POINT BLDG. 2615  
SWIMMING POOL





# TARAWA TERRACE POOL - TT-20

298,800 GALLONS

POOL EQUIPPED WITH  
IFRS PERIMETER  
RIM FLOW

SURGE TANK


800 G.P.M.  
FILTER PUMP


BACK WASH TANK

SEWAGE


3 CELL FILTER  
800 G.P.M. CAPACITY  
50 FT<sup>2</sup> PER CELL


5.59 GALLONS PER FT<sup>2</sup> PER CELL







AREA 2 BLDG. 236  
SWIMMING POOL





AREA 5 BLDG. 540  
SWIMMING POOL





## WATER TREATMENT PLANT


### INDIVIDUAL PLANT DATA

PIANT NO. & LOCATION Hadnot Point Plant Bldg. 20

Write narrative description of overall system - include design capacity of plant, average daily flow; describe chemical treatment, chlorine, etc., other types, quantities used:

The Hadnot Point Plant is a lime softening plant with a capacity of 5.0 M.G.D. and is supplied water from 40 deep wells. The Plant consists of the following equipment:

1. 5 Spiractors at 700 G.P.M. each
2. 5 Rapid sand filters at 700 G.P.M. each
3. 3 Raw water pumps, rated at 2800, 3500, & 4200 G.P.M.
4. 4 High service pumps, rated at 1500, 1500, 1500, & 3000 G.P.M.
5. 2 Wallace & Tiernan V-notch chlorinators, 0-100 lbs/day.
6. 2 Lime storage hoppers
7. 1 Lime storage silo 60 tons
8. 6 Lime pumps, rated at 245 G.P.H. each
9. 1 Backwash pump at 6300 G.P.M.
10. 1 Recarbonation unit, Tomco 27 SCFM
11. 1 - 800,000 gallon Raw Water Reservoir
12. 2 Treated water reservoirs, 1 at 2,000,000 gallons, 1 at 500,000 gallons
13. 4 Elevated Tanks 300,000 gallons each.
14. 1 Wallace & Tiernan volumetric fluoride feeder
15. 1 each Catapillar generator 6 cyl, 275 kw (raw)  
1 each Catapillar generator 175 kw (high lift)




WATER TREATMENT PLANT

INDIVIDUAL PLANT DATA (con't)

PLANT NO. & LOCATION Hadnot Point Bldg. 20 WELLS

Raw Water Wells and Booster Pumps included in the treatment plant system:

<u>H.P.WELLS BLDG. NO.</u>	<u>G.P.M.</u>	<u>AUXILIARY ENGINE</u>	<u>MANUFACTURE</u>
602	154		
603	140	Diesel	Murphy
606	183		
607	270	Diesel	Murphy
608	208 cont.	Gasoline	Ford
609	119		
610	195	Diesel Gen.	Onan
613	190	Diesel	Murphy
616	210		
620	200		
622	300	Diesel	Murphy
623	242	Diesel	Murphy
628	150	Diesel	Murphy
629	200	Diesel	Murphy
632	205		
633	210		
634	219 cont.		
635	146		
636	119		
637	130 cont.		
638	192	Gasoline	Continental
639	105	Gasoline	Continental
640	154	Gasoline	Continental
641	319		
642	128		
651	242 cont.	Gasoline	Ford
652	216 cont.		
653	197 cont.		
654	230	Diesel	Ford
655	110	Diesel	Murphy
660	150	Diesel	Murphy
661	280	Diesel	Murphy




WATER TREATMENT PLANT


INDIVIDUAL PLANT DATA (con't)

PLANT NO. & LOCATION Hadnot Point Bldg. 20 WELLS

<u>H.P.WELLS BLDG. NO.</u>	<u>G.P.M.</u>	<u>AUXILIARY ENGINE</u>	<u>MANUFACTURE</u>
662	168	Diesel	Murphy
5186	214	Diesel	Murphy
LCH 4007	200	Diesel Gen.	Onan
LCH 4009	450	Diesel	Murphy
742 booster pump	700		
709	225	Diesel	MWM
710	200	Diesel	MWM
711	150		
663	300	Diesel	MWM



HADNOT POINT BLDG. #20  
 CAPACITY 5 MGD. WITH 40 DEEP WELLS  
 LIME SOFTENING PLANT






Table III C 3

WELL SURVEY SHEET\*

Sheet No. 1

DATE: 3-3-77

WELL NO.	WELL TYPE	DRILLED DEPTH ft.	STATIC LEVEL (ft)	CASING SIZE (in.)	STAGES	DRAWDOWN AT RATED CAPACITY (feet)	RATED CAPACITY (gpm)	PRESENT CAPACITY (GPM)
<del>HP-601</del> <sup>660</sup>	DRILLED	195'	21'	8"	4	17'	250	100
HP-602	DRILLED	160'	30'	8"	5	15'	150	100
HP-603	DRILLED	195'	19'	8"	5	29'	250	175
HP-606	DRILLED	210'	17'	8"	6	35'	200	150
HP-608	DRILLED	126'	42'	8"	3	16'	250	150
HP-609	DRILLED	150'	11'	8"	4	33'	200	100
HP-610	DRILLED	190'	43'	8"	4	13'	250	175
HP-611	DRILLED	146'	12'	8"	5	11'	250	150
HP-612	DRILLED	190'	14'	8"	5	23'	200	100
HP-613	DRILLED	150'	15'	8"	6	5'	250	150
HP-614	DRILLED	167'	11'	8"	6	19'	250	CAVED
HP-615	DRILLED	158'	21'	8"	4	7'	250	75
HP-616	DRILLED	10'	29'	8"	5	25'	250	100

HP-617-654  
HP-619-653

CAVED  
CAVED

11  
12  
13  
14

WELL NO.	SPECIFIC CAPACITY (gpm/ft of drawdown)	PUMP HEAD (ft)	MOTOR H. P.	CHLORINATION (AMOUNT)	RESIDUAL CHLORINE (ppm)	AUXILIARY POWER (type)	DD FORM	
							710	686
HP-601	14.1	38'	7.5			GASOLINE		
HP-602	10.0	36'	5.0					
HP-603	8.6	86'	10.0			GASOLINE		
HP-608	5.7	2'	10.0					
HP-609	15.6	73'	7.5			GASOLINE		
HP-609	6.1	85'	7.5					
HP-610	19.2	81'	7.5			GASOLINE		
HP-611	22.7	91'	10.0					
HP-612	8.6	84'	7.5					
HP-613	50.0	90'	10.0			GASOLINE		
HP-614	13.2	96'	10.0					
HP-615	35.7	82'	7.5					
HP-616	10.0	85'	10.0					

11  
12  
13  
14




Table III C 3

WELL SURVEY SHEET\*

Sheet No. 2

DATE: 3-3-77

WELL NO.	WELL TYPE	DRILLED DEPTH ft.	STATIC LEVEL (ft)	CASING SIZE (in.)	STAGES	DRAWDOWN AT RATED CAPACITY (feet)	RATED CAPACITY (gpm)	ASSENT CAPACITY (GPM)
HP-620	DRILLED	54'	19'	8"	4	7'	200	100
HP-621	DRILLED	71'	10'	8"	4	20'	250	150
HP-622	DRILLED	207'	16'	8"	4	15'	180	100
HP-623	DRILLED	187'	38'	8"	4	12'	190	100
HP-632	DRILLED	74'	30'	8"	6	10'	250	150
HP-633	DRILLED	205'	25'	8"	3	23'	200	100
HP-634	DRILLED	225'	20'	8"	4	20'	130	50
HP-635	DRILLED	215'	15'	8"	4	25'	200	100
HP-636	DRILLED	227'	8'	8"	5	32'	200	100
HP-637	DRILLED	146'	26'	8"	7	16'	150	75
HP-638	DRILLED	136'	27'	8"	8	35'	185	100
HP-639	DRILLED	76'	23'	8"	7	42'	180	100
HP-640	DRILLED	15'	10'	8"	6	50'	290	250

HP-625-55  
11  
12  
13  
14

Caved

WELL NO.	SPECIFIC CAPACITY (gpm/ft of drawdown)	PUMP HEAD (ft)	MOTOR H. P.	CHLORINATION (AMOUNT)	RESIDUAL CHLORINE (ppm)	AUXILIARY POWER (type)	DD FORM	
							710	686
HP-620	28.6	72'	7.5					
HP-621	12.5	86'	7.5			GASOLINE		
HP-622	12.0	105'	10.0			GASOLINE		
HP-623	15.8	145'	10.0			GASOLINE		
HP-632	25.0	155'	10.0					
HP-633	8.6	98'	7.5					
HP-634	6.5	84'	7.5					
HP-635	8.0	84'	7.5					
HP-636	6.3	84'	7.5					
HP-637	9.3	130'	10.0					
HP-638	5.3	135'	10.0			GASOLINE		
HP-639	4.3	135'	20.0			GASOLINE		
HP-640	5.8	220'	20.0			GASOLINE		

662  
5184  
11  
12  
13  
14




Table III C 3


WELL SURVEY SHEET\*

Sheet No. 3

DATE: 3-3-77

WELL NO.	WELL TYPE	DRILLED DEPTH ft.	STATIC LEVEL (ft)	CASING SIZE (in.)	STAGES	DRAWDOWN AT RATED CAPACITY (feet)	RATED CAPACITY (gpm)	PRESENT CAPACITY (GPM)
HP-641	DRILLED	182'	58'	8"	8-5	26'	<del>168</del> 300	200
HP-642	DRILLED	206'	33'	8"	8	12'	136	100
HP-651	DRILLED	199'	14'	8"	8	60'	200	125
HP-652	DRILLED	183'	22'	8"	7	14'	200	150
LCH-M1	DRILLED	125'	50'	8"	6	35'	300	225
LCH-M2	DRILLED	150'	23'	8"	6	19'	287	160

WELL NO.	SPECIFIC CAPACITY (gpm/ft of drawdown)	PUMP HEAD (ft)	MOTOR H. P.	CHLORINATION (AMOUNT)	RESIDUAL CHLORINE (ppm)	AUXILIARY POWER (type)	DD FORM	
							710	686
HP-641	6.5	105'	15.0					
HP-642	11.3	110'	7.5					
HP-651	3.3	226'	20.0			GASOLINE		
HP-652	14.3	220'	15.0					
LCH-M1	8.6	210'	20.0					
LCH-M2	15.1	220'	20.0			GASOLINE		



WATER TREATMENT PLANT

INDIVIDUAL PLANT DATA


PLANT NO. & LOCATION Courthouse Bay BB-190

The Courthouse Bay Plant is an ion exchange softening plant with a capacity of 800,000 G.P.D., and is supplied water from 5 deep wells:


1. 6 Pressure sand filters at 90.6 G.P.M.
2. 4 ion exchange softeners at 102 G.P.M.
3. 2 Filter pumps at 400 G.P.M. each
4. 3 High service pumps, 2 at 500 G.P.M., 1 at 750 G.P.M.
5. 1 Reservoir, 350,000 gallon capacity SBB-191
6. 2 Elevated tanks, 1 at 100,000 gallon capacity SBB-25, and 1 at 325,000 gallon capacity at Boat Basin
7. 2 Wallace & Tiernan chlorinators
8. 1 Backwash holding tank SBB-188
9. 1 Auxiliary engine Continental 6 cylinder gasoline
10. 1 Generator 4 cylinder gasoline

Raw water wells included in the treatment plant system:

<u>CHB.WELLS</u> <u>BLDG. NO.</u>	<u>G.P.M.</u>	<u>AUXILIARY</u> <u>ENGINE</u>	<u>MANUFACTURE</u>
44	128		
220	140		
221	340	Diesel Gen.	Onan
43 (new)	280	Diesel	Murphy
221A (new)		Diesel	



COURTHOUSE BAY BLDG. BR-190  
 CAPACITY 800,000 GPM  
 WITH 5 DEEP WELLS  
 ZEOLITE SOFTENING PLANT







Table III C 3  
WELL SURVEY SHEET

Sheet No. 10

DATE:: 20 JUNE 1984

WELL NO.	WELL TYPE	DRILLED DEPTH ft.	STATIC LEVEL (ft)	CASING SIZE (in.)	STAGES	DRAWDOWN AT RATED CAPACITY (feet)	RATED CAPACITY (gpm)	PRESENT CAPACITY (gpm)
<del>BB-43</del>	DRILLED	54'	18'	8"	4	19'	175	100
BB-44	DRILLED	63'	24'	8"	4	10'	200	100
BB-220	DRILLED	63'	34'	8"	3	6'	150	150
BB-221	DRILLED	65'	35'	6"	3	8'	300	300
<del>A-5</del> NEW 43 21A	DRILLED	116'	18'	8"	4	14'	250	150

WELL NO.	SPECIFIC CAPACITY (gpm/ft of drawdown)	PUMP HEAD (ft)	MOTOR H. P.	CHLORINATION (AMOUNT)	RESIDUAL CHLORINE (TYPE)	AUXILIARY POWER (TYPE)	DD FORM	
							710	636
<del>BB-43</del>	9.2	63'	5.0	5 lbs per day	0.6	GASOLINE		
BB-44	20.0	60'	5.0					
BB-220	25.0	78'	7.5					
BB-221	31.5	82"	15.0					
<del>A-5</del> NEW 43 221A	17.9	75'	3.0					



WATER TREATMENT PLANT

INDIVIDUAL PLANT DATA

PIANT NO. & LOCATION Onslow Beach BA-138

The Onslow Beach Plant is an ion exchange softening plant with a capacity of 250,000 G.P.D., and is supplied water from 2 deep wells. The plant consists of the following equipment:

1. 2 Pressure sand filters at 37 G.P.M.
2. 2 ion exchange softeners at 75 G.P.M.
3. 1 Treated water reservoir, SBA-139, 250,000 gallons capacity
4. 1 Elevated tank, SBA-108, 100,000 gallons capacity
5. 3 High service pumps, 1 at 300 G.P.M., 1 at 750 G.P.M., & 1 at 1000 G.P.M.
6. 1 Auxiliary engine, Ford, Diesel
7. 2 Wallace & Tiernan chlorinators

Raw water wells included in the treatment plant system:

<u>O.B.WELLS</u> <u>BLDG. NO.</u>	<u>G.P.M.</u>	<u>AUXILIARY</u> <u>ENGINE</u>	<u>MANUFACTURE</u>
164	159	Diesel	Ford
190	210		





Table III C 3  
WELL SURVEY SHEET

Sheet No. 11

DATE: 20 June 1984

WELL NO.	WELL TYPE	DRILLED DEPTH ft.	STATIC LEVEL (ft)	CASING SIZE (in.)	STAGES	DRAWDOWN AT RATED CAPACITY (feet)	RATED CAPACITY (gpm)	PRESENT CAPACITY (gpm)
BA-164	DRILLED	61'	17'	8"	8	8'	200	175
BA-190	DRILLED	115'	7'	8"	7	20'	250	-

WELL NO.	SPECIFIC CAPACITY (gpm/ft of drawdown)	PUMP HEAD (ft)	MOTOR H. P.	CHLORINATION (AMOUNT)	RESIDUAL CHLORINE (TYPE)	AUXILIARY POWER (TYPE)	DD FORM	
							710	636
BA-164	25.0	130	10.0			GASOLINE		
BA-190	12.5	157.5	15.0					





ON SLOW BEACH BLDG. RA-138

CAPACITY 250,000 GPD.

WITH 2 DEEP WELLS.

ZEOLITE SOFTENING PLANT





WATER TREATMENT PLANT

INDIVIDUAL PLANT DATA

PIANT NO. & LOCATION Rifle Range Bldg. RR-85

The Rifle Range water plant is an ion exchange softening plant with a capacity of 600,000 G.P.D., and is supplied water from 4 deep wells:

The plant consists of the following equipment:

1. 3 Pressure sand filters at 134 G.P.M. each
2. 2 ion exchange softeners at 128 G.P.M. each
3. 2 Filter pumps at 400 G.P.M. each
4. 3 High service pumps, 2 at 500 G.P.M., and 1 at 750 G.P.M.
5. 1 Treated water reservoir at 350,000 gallons, SRR-86
6. 1 Elevated tank, 100,000 gallon capacity SRR-44
7. 2 Wallace & Tiernan chlorinators
8. 1 Backwash holding tank SRR-102
9. 1 Auxiliary engine Continental 6 cylinder, gasoline
10. 1 Generator, Onan 125 kw

<u>R. R. WELLS</u> <u>BLDG. NO.</u>	<u>G.P.M.</u>	<u>AUXILIARY</u> <u>ENGINE</u>	<u>MANUFACTURE</u>
45	201	Gasoline	Allis Chalmers
47	104		
97	151		
229	300 cont.	Diesel	Murphy





Table III C 3  
WELL SURVEY SHEET

Sheet No. 9

DATE: 20 June 1984

WELL NO.	WELL TYPE	DRILLED DEPTH ft.	STATIC LEVEL (ft)	CASING SIZE (in.)	STAGES	DRAWDOWN AT RATED CAPACITY (feet)	RATED CAPACITY (gpm)	PRESENT CAPACITY (gpm)
RR-45	DRILLED	130'	27'	8"	10	8'	140	100
RR-47	DRILLED	85'	11'	8"	7	6'	250	175
RR-97	DRILLED	200'	52'	8"	13	14'	150	150
New well to replace 227 still under contract 229								

WELL NO.	SPECIFIC CAPACITY (gpm/ft of drawdown)	PUMP HEAD (ft)	MOTOR H. P.	CHLORINATION (AMOUNT)	RESIDUAL CHLORINE (TYPE)	AUXILIARY POWER (TYPE)	DD FORM	
							710	636
RR-45	17.5	205'	15.0			GASOLINE		
RR-47	41.7	109'	20.0					
RR-97 229	10.7	180	10.0					



CAPACITY 600,000 GPD  
 WITH 4 DEEP WELLS  
 ZEOLITE SOFTENING PLANT

