

### COST ESTIMATE

DATE PREPARED  
3-5-87

SHEET OF

ACTIVITY AND LOCATION

CONSTRUCTION CONTRACT NO.

IDENTIFICATION NUMBER

Bldg 67 (Through Bldg except audit area)

ESTIMATED BY

CATEGORY CODE NUMBER

Huffman

PROJECT TITLE

STATUS OF DESIGN

JOB ORDER NUMBER

PED  30%  100%  FINAL  Other (Specify) \_\_\_\_\_

Rpr/Ren Htg, Plbg, Piping, Remove asbestos

ITEM DESCRIPTION	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
	NUMBER	UNIT	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
(Void "Audit" area of building) Demo all asbestos piping insulation. Demo all steam, condensate, potable water, fire line piping, radiators, steam heating air handlers at chapel. Demo hot water heating storage tank asbestos to be removed complete from walls, attics, (etc).				6,000		18,000		24,000
Replace all potable water piping & insulate Replace all galvanized &/or steel waste, drains, vents. Replace all plumbing fixtures with state of the art to include all valves, faucets, traps & trim. Replace all wall hydrants (ext).				29,200		31,680		60,880
In steam pit replace hot water storage tank all steam PRV's and piping.				11,000		1,200		12,200

